

Note straight, even wall surfaces and neatly tooled joints (Typical for all concrete and unit masonry)

5.4.2 (10) - Handrails and adjacent wall surfaces shall be free of any sharp or abrasive elements.

5.4.2 - Handrails


Handicap Accessible RAMP Requirements

5.2.1 - Ramps shall have a 1:12 maximum slope



For exception see 10.5.1 (Below)

5.2.2 - Exterior ramps shall have a minimum 48" clear width

5.2.3 - An interior accessible route (including ramps) shall have a minimum 36" clear width





5.4.1 - Handrails are not required if the ramp conforms to the following:



5.4.1 - Ramps having a rise greater than 6" or a run greater than 72" shall have handrails on both sides. (Not required in assembly seating areas)

5.4.1 - Ramps requiring handrails



5.4.2 (8) - Handrail termination

